



Scale 1 : 20

SEPTIC TANK TO
BE CLEARED EVERY 3 YEARS

1. Septic tank sized with 2 days retention capacity for full occupancy to prevent solids being discharged to small bore sewer.
2. Brickwork plastered internally,
3. Tee pieces and piping heavy duty PVC.
4. Top slab reinforced with standard mesh reinforced reference No. 193 placed 40mm above soffit.
5. All concrete 30Mpa.

REV	DATE	DESCRIPTION	APPROVED		
Checked by Consultant					
Signature			Date		
	BY	DRAWN	CHECKED		
SURVEYED					
DESIGNED	G.D.B	F.M.Y			
ENGINEER	G.D.B				
NAME OF DESIGN-CONSULTANT/AGENT					
GDB ENGINEERS cc					
CK 2007/116202/23					
P.O. BOX 11415 DORPSPRUIT 3206			149 GREYLING STREET PIETERMARITZBURG 3201		
TEL : (033) - 342 8647 FAX : (086 819 8249) E-MAIL : geoff@gdbengineers.co.za					
PROJECT:					
PROPOSED SEPTIC TANK FOR GOWRIE FARM					
PLAN DESCRIPTION:					
PLAN AND SECTIONS					
FILE No.		SCALE		SHEET	
		AS SHOWN			
PROJECT No.		DRAWING No.		REVISION	
1353C		16			